

Maharaja Ranjit Singh Punjab Technical University, Bathinda

Supplying, Fixing, Testing & Commissioning of Fibre Wire Connectivity for Server Room to Boys Hostel No. 1 to 5 and Girls Hostel No. 2.

Sr.No.	Description of Item	Qty.
1	24FOFC SM/MT/UA/ADSS/SS/ORNG HDPE 652D F	1400
2	FMS(LIU) Rack Mountable, Loaded -24F	2
3	FMS(LIU) Rack Mountable, Loaded -12F	5
4	Duct HDPE 40mm w/o Rope	900
5	Duct Coupler	20
6	Pigtail FCPC 3 Mtr	108
7	FCPC Connector	108
8	Router Marker	10
9	Boring of 6" dia for more than 6m	400
10	Fiber Pulling	1200
11	media Convertor 10/100mbps	7
12	FC to SC patch card	36
13	Trenching 1.5M(1D/1C)	600
14	Route marker Installation	10
15	OFC Splicing	108
16	Supply & Installation	Lumpsum

Note:- The Quantity may be vary at the time of execution of work. Work is to be done on TURNKEY Basis.