## (50)

### Annexure-A

# <u>Upgradation of Old cooking sheds of Boys Hostel No. 01, 03, 04 and Girls Hostel No. 1& 2 of the Campus</u>

S.No.	Description of Items	Qty. (approx.)	Rate	Amount
1/8.5	Dismantling brick work tile masonary or tile lining In cement.	5 Cum	422.70	2113.50
b) 2/8.6 d)	Dismantling concrete or precast concrete.  Cement concrete plain 1:2:4	4 Cum	845.41	3381.64
3/8.11	Stripping and stacking iron sheets of a roof including ridging, flashing, eaves boards gutters and down pipes.	350 Sqm	18.76	6566.00
4/10.12 (ii)	Cement concrete 1:2:4 with stone ballast or shingle using Concrete Mixer volumetric type	5 Cum	3866.12	19330.60
5/8.31 c)	Scraping cement plaster	25 Sqm.	22.31	557.75
a)	Scraping white wash	100 Sqm	4.41	441.00
6/9.3	Centring and shuttering for faces of walls, partitions, retaining walls and the like (vertical or battering) including attached pillasters, buttersses etc when curved.	20 Sqm	287.35	5747.00
7/15.9	12.5 mm thick cement plaster 1:4	150 Sqm.	118.16	17724.00
8/18.4	Wrought iron and mild steel ladders, framed grills, grating etc. Note: (if new grill is not provided the lab our rate to be given for re-fixing the old grill)	5 Qtl.	7585.26	37926.30
9/16.21 (a)	Applying priming coat with metal primer on new steel or iron work including preparation of surface. With special quality paint Painting two coats excluding priming coat with	50 Sqm.	17.23	861.50
16.18 (a)	synthetic enamel paint in all shades on wood work, metallic or plastered, concrete surface to give an even shade.	125 Sqm.	58.10	7262.50
10/1/0	With special quality paint White washing (two coat)	400 Sqm.	8.11	3244.00
10/16.2		200 Sqm	16.71	3342.00
11/16.5	Colour washing (two coats)  Preparation of plastered surfaces for distempering including surface, applying filling with approved quality filler consisting of plaster of Paris and chalk mitti including finishing the surface to the required finish complete.	50 Sqm	35.03	1751.50
13/16.15	Finishing walls with exterior decorative cement based such as snowecem, robbiacem etc. on old work one coat to give an even shade.	150 Sqm	28.50	4275.00
14/16.16	Preparation of plywood surface for painting including sand papering the surface and applying filling with approved quality fillers consisting of white lead, linseed oil, Varnish, and Chalk Mitti including finishing the surface to required finish complete.	40 Sqm	33.86	1354.40
15/17.12 iii) b)	Golden Champ cup board shutter with plywood panels or faced on both side fixed in position (excluding the cost of handles, bolts hasp with staple but including the labour for fixing them)  25mm thick	20 Sqm	1908.66	38173.20

	1		L
1	10	1	
1	_	"	1
L	_		

16/18.29 (a)	Providing and fixing M.S. angle iron 40x40x6mm (or 40x40x4mm as per requirement) chowkhat including iron hold fasts butt hinges fixed in position, finished with red lead non setting primer complete in all respect For single rebate.	125 Kg	84.39	10548.75
17/18.3 a)	Structural steel work in angles, tees and flats, riveted or welded including cutting fixing all gusset plates, bolts, nuts, rivets, welding rod, etc. with hoisting and erecting in position:  For roof trusses, well curbs, plates and trussed girders, etc. of any span for buildings and bridges up to 15 m span.@ 3694-4500=806+80.60 (10%) = 886.60 + 8.86 (1%) = 895.47 P.Qtl	65 Qtl	7056.43	458667.95
18/NS	Providing & Fixing of Coloured 0.45mm thick AZ 150 GSM Semi Corrugated sheets	421.30 Sqm	749.66	315831.75
19/17.23 ii)	Cost of Aluminium fittings complete for doors, windows such as tower bolts, handless and screw etc. for these fittings (Excluding sliding bolt) For shutter area above 0.50 sqm	20 Sqm	144.03	2880.60
20/11.5	First class burnt brick work laid in cement sand mortar 1:5 in foundation and plinth.	10 Cum	3581.82	35818.20
21/NS	Credit of Iron Scrap	7.5 Qtl	1500/- per Qtl	- 11250.00
Total Amount				

Note: Quantity may vary at the time of execution of Work.

Say Rs. <u>966549/-</u>

(Nine Lac Sixty Six Thousand Five Hundred and Forty Nine Rupees Only)

2 manilo

Windows -

# Approximate area of cooking sheds in various Hostels

Girls Hostel No. 1: 41' x 28' = 1148 Sq. feet

Girls Hostel No. 2:  $30' \times 22' = 660 \text{ Sq. feet}$ 

Boy's Hostel No. 1:  $19' \times 25' = 475 \text{ Sq. feet}$   $14' \times 22' = 308 \text{ Sq. feet}$ 783 Sq. feet

Boy's Hostel No. 3:  $24 \times 36' = 864 \text{ Sq. feet}$ 

Boy's Hostel No. 4:  $30' \times 36' = 1080 \text{ Sq. feet}$ 

4535 Sq. Feet or 421.30 Sqm

SAE

Ginden Singh