

1

Annexure-A

AOR FOR REPLACING GRIT WASH WITH CEMENT PLASTER AT GIRLS HOSTEL No 1 OF GZSCCET, MRSPTU CAMPUS BATHINDA

S. No.	Ref to CSR	Description of Item	Qty	Unit	Rate	Amount
1	NS	Dismantalling grit wash plaster and disposal of malba	2820	Sqm	50.22	141628
2	15.48	Cement rendering on plaster 1mm thick	2820	Sqm	39.28	110775
3	15.2	20mm thick cement plaster 1:4 in two coat work				
		GF	600	Sqm	160.53	96321
		FF	600	Sqm	162.21	97329
		SF	680	Sqm	163.89	111448
4	15.75	Forming groove of uniform size from 12x12mm and upto 25x15mm in plastered surface as per approved pattern using wooden battens, nailed to the under layer including removal of wooden battens, repairs to the edges of plaster panel and finishing the groove complete as per specifications and direction of the Engineer-in-Charge	11952	Rmt	18.05	215686
5	15.70	Washed stone grit plaster on exterior walls of height upto 10 M. above ground level in two layers, under layer 12.5mm cement plaster 1:4 (1 cement : 4 coarse sand) furrowing coarse sand : 2 stone chipping 10mm nominal size) in panels with groove all aroundKg of cement per square metre, top layer 15mm cement plaster 1:1/2:2 (1 cement: 1/2the under layer with scratching tool, applying cement slurry on the under layer @ 2 as per approved pattern including scrubbing and washing, the top layer with brushes and water to expose the stone chippings, complete as per specification and direction of Engineer-in-charge (Payment for providing grooves shall be made separately).	200	Sqm	338.80	67759
Total						840946

Note: 1. Any error regarding description,reference to CSR quantity, rate,premium, unit calculations omission , addition will be corrected at any stage as per CSR,AOR, specifications and drawings and no claim whatsoever shall be entertained on this account.

2. Quantity may vary at the time of execution of Work

Say Rs. 840946/-

(Rs. Eight Lac Forty Thousand Nine Hundred and Forty Six Only)

Nov av

S.D.E

Singh
12/10/18

A.E (Civil)

Hindewar

J.E (Civil)

Jedh
Executive Engineer

Jedh
Superintending Engineer