



Maharaja Ranjit Singh Punjab Technical University
Dabwali Road, Bathinda.

(Established by Govt. of Punjab vide Punjab Act No. 5 of 2015 and approved Under Section 2(f) & 12(B) of UGC)

Ref. No. MRSPTU/Estate/26-27/969 to 975

Dated 12/05/28

(Regd.)

To

As per List Attached.

Sub: - Quotations for Construction of Working Tables in Room No. A-308 of Chemistry Deptt., MRSPTU, Bathinda.

Dear Sir,

01. You are requested to quote the rates for the items shown in the Appendix 'A' separately attached to this letter. The rate must be quoted only on the attached paper as per our specifications.
02. Following shall be taken note of while quoting the rates:-
 - a) The rates will be F.O.R. MRSPTU, Bathinda.
 - b) Job Completion period should be mentioned clearly.
 - c) Warranty/Guarantee/All contractual obligations should be mentioned clearly.
 - d) Payment will be made after successful inspection of the team.
 - e) For research items, the relevant exemption certificate DSIR will be issued to the successful firm to charge GST @5% only, if applicable, otherwise GST will be charged at applicable rates.
 - f) Quotation received later than due date are liable to be ignored/rejected.
 - g) Quotation must be submitted on **LETTER HEAD** of the firm in the name of **REGISTRAR, MRSPTU, BATHINDA** with all particularly duly signed with stamp in sealed envelope, any other format will not be acceptable.
 - h) The envelope must bear the word:-
QUOTATION FOR " Construction of Working Tables in Room No. A-308 of Chemistry Deptt., MRSPTU, Bathinda. "
Enquiry No. _____ As above dated _____
Due on _____
Address: As mentioned as point no. 04
IMPORTANT: -In the absence of information as required under 2(h) above, if an envelope is received & opened inadvertently, the university will not be responsible and the quotation may not be considered even if quoting lowest rates.
 - i) Please mention any other charges/conditions
 - j) Loose, tempered or incomplete quotation will not be considered.
 - k) Any other information as per requirement of indentor/department.
 - l) The quality of the items to be quoted should be best available in the market.
03. General Terms & Conditions are attached along with.
04. The quotations should reach the **office of Registrar, Maharaja Ranjit Singh Punjab Technical University, Bathinda-151001** by **19-05-2026 up to 5 pm** and same shall be opened there after in the presence of Committee members.

Indentor

Head of Department

Copy to:-

1. Professor Incharge, IT Enabled Services, MRSPTU, Bathinda to upload a copy on University & College Websites.

Contd. Page...2

TERMS & CONDITIONS

1. **DELIVERY/JOB COMPLETION PERIOD:-**
Minimum Period for delivery/job completion should be mentioned clearly.
2. **VALIDITY OF QUOTATIONS:-**
Quotations will be considered valid for 03 months from the date of quotation.
3. **GUARANTEE/WARRANTY:-**
Guarantee/Warranty should be mentioned clearly.
4. **DISCOUNT/REBATES:-**
A Special discount/rebate wherever admissible keeping in view that the supplies are being made for education purpose in respect of Public Institution of national importance may please be indicated.
5. **VICE CHANCELLOR'S RIGHTS:**
Vice Chancellor, MRSPTU, Bathinda reserves the rights of acceptance or rejection of any or all quotations. The discretion for increasing or decreasing of the quantities also rests with him. MRSPTU also not bind itself to accept the lowest price. In case of any dispute, the decision of Vice Chancellor, MRSPTU, Bathinda will be final & binding.
6. **SAMPLE/BRAND/MAKE/WEIGHT:-**
Sample where asked for, will invariably be made available and sent along with the quotations. However, Brand/Make/Weight etc. must be mentioned clearly in the quotations. Technical literature/pamphlet should also be enclosed.
7. **REJECTION:-**
Quotation not conforming to the set procedure as above will be rejected.
8. **CORRESPONDENCE:**
No correspondence regarding acceptance/rejection of a quotation will be entertained.

MRSPTU shall not be held responsible for any postal delay in sending or late receipt of quotation. Quotation should be free from corrections & erasures.

QUOTATION

To

The Registrar,
MRSPTU, Bathinda.**Sub: Construction of working tables in room no. A-308 of Chemistry Deptt., MRSPTU, Bathinda.**

S.No./ CSR Ref	Item Description/ Specification	Unit	Qty.	Basic Rate (per unit in Rs.)	Disco unt/C SR +/-, (if any)	GST (in %age) (if applic able)	Rate (includ ing GST/ discou nt)	Total Amount Including GST/Disc ount/CSR +/-)
	<u>For Civil Works</u>							
1/ 8.18	Dismantling brick or flagged stone flooring including concrete base.	Sqm	0.66					
2/ 11.36	Dismantling brick or flagged stone flooring including concrete base.	Sqm	2.6					
3/11.4i)	First class burnt brick work laid in cement sand mortar 1:6 in first storey upto 4 metres above plinth level.	Cum	0.75					
4/ 11.29a)	Extra for work done in additional storey upto 4 metre above the top of structural roof of lower storey for Brick Work/ Concrete Block/ Clay Block (upto 3rd storey) (Rs.153.81/- for one storey)	Cum	0.75					
5/ 15.1	12.5 mm thick cement plaster 1:5	Sqm	6.4					
6/ 9.8	Centering and shuttering for flat surfaces such as suspended floors, roofs, landings, chajjas, shelves etc.	Sqm	7.35					
7/ 18.17	Cold twisted deformed (Ribbed/ Tor steel) Bars (Fe 415 grade as per IS 1786-2008) , for R.C.C works, where not including in the complete rate of RCC including binding & bending and placing in position complete	Qtl	0.6					
8/ 10.2	Reinforced cement concrete M-20 mechanically batch mixed using batch type concrete mixer as per IS:1791 and vibrated by needle vibrator but excluding steel reinforcement centring and shuttering in superstructure.	Cum	0.7					

14.89a	Providing and laying flamed finish Granite stone 18mm thick in flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge :Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent	Sqm	6.9					
9/14.75	Extra for pre finished nosing to treads of steps of marble stone. (Full gola, half round gola etc.)	Mtr	3.4					
10/30.32 iii)	Providing and fixing in position vitreous chinaware white lavatory suites of approved make (to the approval of Engineer-in-charge) consisting of C.P. brass waste 32mm dia with one C.P. brass pillar tap including Rack Bolt Screw Pair 115mm long complete in all respect. Size 630 mm x 450 mm x 830 mm	Each	1					
11/30.20	Providing and fixing P.V.C Waste Pipe Collapsible 32mm complete in all respect.	Each	1					
12/28.58 b	Cutting holes upto 23cm square for pipes in floor and roofs of cement concrete, reinforced concrete or reinforced brick work and making good the same & finishing according to existing finish where required. Through floor or roof 11.5cm thick	Each	1					
13/30.74 (iii) d)	Providing and fixing in position singel socket SWR UPVC soil waste or antisiphonage pipes as per IS 13592 of E.D.C manufacture or of any other reputed firm including cutting, jointing, wastage, but excluding cost of jointing. Single Socket Type A 75mm o/d single socket SWR UPVC pipe lines laid complete.	Mtr	5					

4/28.21 A) (a)	Providing and laying, jointing, fixing and testing ISI Marked uPVC Pipe Lines as per ISI 4985-2000, including specials such as tees, bends, sockets, elbow etc., cutting, testing (including cost of specials) in the ground complete in all respects. uPVC Pipe 10 Kgf/cm ² 20mm i/d	Mtr	8.9					
15/28.21 A) (e)	Providing and laying, jointing, fixing and testing ISI Marked uPVC Pipe Lines as per ISI 4985-2000, including specials such as tees, bends, sockets, elbow etc., cutting, testing (including cost of specials) in the ground complete in all respects. uPVC Pipe 10 Kgf/cm ² 50mm i/d	Mtr	9.1					
16/28.43 b	Providing, fixing and jointing ISI Marked Gun-Metal peet valves (Heavy Pattern) as per IS 778 with hand wheels, on G.I. Pipe lines laid in the ground or inside buildings including all carriages complete. 20mm i/d Gun Metal peet valve heavy pattern.	Each	1					
	<u>For Electrical Works</u>							
1/34.07 A	SURFACE PVC CONDUIT PIPE WIRING SYSTEM WITH MODULAR SWITCHES:							
	Wiring in PVC insulated copper conductor single core FR cable (ISI marked) overall 1.5sq. mm, 1100volts grade to be laid in heavy gauge PVC conduit pipe 20mm/25mm dia (ISI Marked) installed on surface etc., complete with PVC boxes (Plastic on surface boxes) required for suitable number of modules (Modular accessories) for having Step type electronic fan regulators (two module) 100watts, bell push, 6Amp. 2/3 universal socket (shuttered), 16/20Amp. combined/ universal Socket (shuttered), 6/10Amp. Switches, 16/20Amp. switches with indicator etc. and covered with Frame Plate etc.,							

	PVC connector (For Fan Box and Call Bell), MS saddle clamp, PVC Circular junction Boxes (Four way 1½" deep for walls), bonding to earth with PVC insulated copper conductor single core FR cable (ISI marked) 1sq. mm, 1100volts grade (For 6Amp. wall socket & plug control point) and other petty material etc., including the cost of above aterial and painting as required:- Make Legrand , Anchor, SSK, North West							
v)	Wiring 6Amp. Plug control comprising wall socket point	6	Each					
vi)	Wiring 16/20Amp. power plug control point	6	Each					
2/ 34.09	PVC INSULATED FR COPPER CONDUCTOR CABLES:							
	Supply and erection of PVC insulated FR single core Unsheathed copper conductor cable (ISI marked) suitable upto 1100 volts grade confirm to IS:694/1990 left bare in pipe or casing of suitable size complete in all respect as desired by the Engineer-in-charge:-make :-Finolex, Polycab, Havell's							
i)	Overall size 1sq.mm (Un-sheathed)	13	Metre					
iv)	Overall size 4sq.mm (Un-sheathed)	20	Metre					
3/ 34.12	PVC, HDPE PIPES & PVC FLEXIBLE PIPES:							
	Supply & erection of PVC Conduit Pipes (ISI marked) as per IS9537:Part-III & HDPE pipes (ISI marked) as per IS:4984:1995 for wiring purposes including bends, junction boxes, Steel hooks, M.S. saddle clamps and other petty materials etc., as per PWD General Specifications:- Make AKG, Poly India heavy, Finolex, polycab, Diplast.							
i)	Heavy Gauge PVC Conduit Pipe 20mm dia. (On Surface)	6	Metre					
ii)	Heavy Gauge PVC Conduit Pipe 25mm dia. (On Surface)	4	Metre					

Note: 1) University GST No. 03AAAGT0124M1ZJ.
2) Quantity may vary at the time of execution of work.

General Conditions:

- a) The rates will be F.O.R. (Estate Deptt.) MRSPTU, Bathinda.
- b) Job Completion period should be mentioned clearly.
- c) Warranty/Guarantee/All Contractual Obligations should be mentioned clearly.
- d) Any other.

Name of Bidder _____

Signature with Stamp _____